

# TRIBUILT® TUBOS PIPE EXTENSION

Measure, Cut, Seal. Meeting Code Made Easy!

TRI-BUILT® Tubos are prefabricated plumbing vent pipe extensions and the fastest, strongest, and most cost-effective method for extending plumbing vent pipes during reroofing operations.

When additional layers of insulation are added to the roof, many vent stacks fall out of code compliance. National and local building and plumbing codes require that vent stacks are a certain height above the roof surface. This is the ideal situation for using TRI-BUILT® Tubos!

TRI-BUILT® Tubos are made with an integral six-inch long joint splice sleeve insert at each end, allowing for one TRI-BUILT® Tubos unit to be cut and used to extend two vent stacks!

## Simple Three-Step Process

1. Insert the TRI-BUILT® Tubos into the existing vent pipe.
2. Measure and cut the Tubos to the correct height (check local plumbing code requirements).
3. Lift the TRI-BUILT® Tubos and apply caulk around the top lip of insert sleeve to keep the methane gas in, then flash as normal.

That's it – you've just turned a complicated 15- to 30-minute job using alternative methods into a simple 3- to 5-minute project, and you have another TRI-BUILT® Tubos in hand for the next vent stack. It's fast, efficient, economical and does not require any special tools.

TRI-BUILT® Tubos products (patent pending) are also designed to keep water from leaking into the roof assembly and will fit the inside diameter of 2-, 3- and 4-inch PVC and cast iron vent pipes.

TRI-BUILT® SKU	SIZE (Diameter)	Overall Length/ Unit	Quantity/Box	Box Weight
88845500	2"	28"	18	46 lbs.
88845505	3"	28"	12	48 lbs.
88845510	4"	28"	9	48 lbs.



Unique design virtually eliminates leaks and call-backs.



## Features & Benefits

- Just three easy steps: measure, cut to length, seal in place with caulk. Meets code!
- Three sizes (2-, 3- and 4-inch), are compatible with both cast iron and PVC vent pipes and accommodates the majority of vent pipes.
- Turns a complicated 15- to 30-minute job using alternative methods into a simple 3- to 5-minute project.
- Properly installed TRI-BUILT® Tubos will not leak.
- Easy to install with common tools (tape measure, saw, caulk and caulk gun).
- Labor saving and economical compared to alternate methods.

